



NOTES:

1. SAWCUT FULL DEPTH MINIMUM 2'0" FROM EDGE OF EXCAVATION.
2. TOP 4'0" OF TRENCH SHALL BE BACKFILLED WITH CSTC (WSDOT 9-03.9(3), CDF (PER COB STANDARD #) OR NATIVE MATERIAL. IF CITY ENGINEER PREAPPROVES THE USE OF NATIVE MATERIAL, THE TOP 6" OF TRENCH SHALL BE CSTC.
3. TRENCH WIDTH PER COB STANDARD DRAWING # 6060 .
4. A TACK COAT OF EMULSIFIED ASPHALT SHALL BE APPLIED & ALLOWED TO "BREAK" PRIOR TO PLACING ASPHALT CONCRETE.
5. TRENCH CONSTRUCTION / RESTORATION MUST BE COMPLETED IN 14 DAYS OR LESS.
6. HMA SHALL BE CLASS 1/2", PG 64-22.



City of Bremerton

PUBLIC WORKS

ENGINEERING DIVISION

**TRENCH RESTORATION
ASPHALT CONCRETE**

Alteration of this drawing is prohibited. Any approval of an altered drawing is unauthorized and void.

3155

Revision Date

11/20/13