



### NOTES:

1. 8 MIL PLASTIC OR CONSTRUCTION FABRIC SHALL BE WRAPPED AROUND PIPE AND FITTINGS BEFORE THRUST BLOCKS ARE POURED.
2. SUPPORT VALVE AND SLEEVE CONTINUOUSLY THROUGH INSTALLATION.
3. NO CONNECTIONS WITHIN THIS AREA
4. INSTALL TWO PIECE CAST IRON VALVE BOX & CAST IRON LID EMBOSSED WITH "SEWER"  
CITY STANDARD - SEE DETAIL 6130
5. STAINLESS STEEL TAPPING TEES SHALL HAVE FULL CIRCLE SEAL. BOLTS AND NUTS SHALL BE STAINLESS STEEL.
6. STEEL TAPPING TEES SHALL BE EPOXY COATED. BOLTS AND NUTS SHALL BE COR-TEN, OR STAINLESS STEEL.



**City of Bremerton**

**PUBLIC WORKS**

**DESIGN/CONSTRUCTION STANDARDS**

### CONNECTION TO EXISTING SANITARY SEWER FORCE MAIN

Alteration of this drawing is prohibited. Any approval of an altered drawing is unauthorized and void.

**6126**

Revision Date  
03/09/15